Preliminary Design Review

Clean Tech Titans November 7th, 2023





Team Introduction & Client

7x24 Exchange Rocky Mountain Chapter

- Tom Dobson
- Alberto Barrios Marquez
- Justin Peltzer



Clean Tech Titans

- Aidan Mahoney DE
- Emma Day CE
- Luke Folsom ME
- Adam Carranco ME
- Fischer Argosino ME





Agenda







Agenda

- 1. Problem Definition
- 2. Initial Research & Design Considerations
- 3. Design Decision
- 4. Schedule and Next Steps Update

Problem Definition

Problem Definition

Data Centers account for 1% of the world electricity demand. Thus, accounting for a significant amount green-house gas emission. This also comes at a time of increased regulation on data center energy consumption and accelerated demand for the services they provide.



Subsystem Breakdown

Energy Generation

Generation techniques required to meet the total energy demands of the data center facility.

Mechanical Design

Components relating to the meeting the cooling load of the critical IT equipment and support space. Including HVAC equipment, ducting, and energy efficiency measures.

Electrical Design

Required components to store and distribute electricity to critical IT load and mechanical systems.

Civil Design

Building siting, envelope and floor plan layout required in order to meet space requirements of critical components.



Client Goals





Initial Research & Design Considerations

Tiering Standard



Tier I Basic Capacity

Site-wide shutdowns are required for maintenance or repair work. Capacity or distribution failures will impact the site. Tier II Redundant Capacity Components

Site-wide shutdowns for maintenance are still required. Capacity failures may impact the site. Distribution failures will impact the site.

Tier III Concurrently Maintainable

Each and every capacity component and distribution path in a site can be removed on a planned basis for maintenance or replacement without impacting operations. The site is still exposed to an equipment failure or operator error.

Tier IV Fault Tolerant

An individual equipment failure or distribution path interruption will not impact operations. A Fault Tolerant site is also Concurrently Maintainable.

https://uptimeinstitute.com/tier-certification



Initial Research – Site Visits

Learning:

COLORADOSCHOOLOF**MINES**

ARTH • ENERGY • ENVIRONMENT









Initial Research – Literature Review

- Power Generation
 - Sources: Wind, Solar (PV, Concentrated), Geothermal, Hydrogen Fuel Cells
 - Considerations: Capacity, space and land requirements scalability, and ideal sites.
- Energy Storage Technologies
 - Technologies: Lithium-Ion Batteries, Lithium Sulfur batteries, hydrogen, thermal storage
 - Considerations: Energy density, efficiency, cost, and space.
- Energy Efficiency Measures
 - Measures: Plate-Frame heat exchanger, Economizing, hot/cold aisle containment, warmer chiller water, and ground-source heat pump.
- Cooling
 - Direct-to-Chip
 - Immersive
 - Traditional Air Cooled

COLORADOSCHOOLOFMINES





Major Design Considerations

- Tiering Standard
- Zero-Carbon
- Viability of power generation options
- Cooling efficiency
- Cooling load
- Data center siting/placement
- White space layout
- One-line components

Concepts Explored

<u>Package 1 - Solar, Wind, & Hydrogen</u>





Concept Package 1: Solar + Wind + Hydrogen



Location: Southeast Bent County

Cooling Method: Traditional Air Cooling (CRAC/CRAH)

Wind: GE 1.6 MW 100m

- Energy Density of 500 W/m^2
- 1x the of demand will be supplied through wind
- Requires 74 acres of 8 MW windfarms

Photovoltaic Solar:

- Energy Density of 5.5-6 kWh/m²/Day
- 0.5x the demand will be supplied through Solar
- Requires ~25 acres of 4 MW solar arrays (swivel?)

Hydrogen Fuel Cells:

- Excess capacity for Hydrogen production with onsite electrolyzer
- 0.5x of total capacity can be supplied by hydrogen fuel cell



Concept Package 1: Solar + Wind + Hydrogen

Benefits

- Integration of diverse renewable energy technologies ensures redundancy for enhanced reliability.
- Minimal water consumption is a key operational feature, promoting sustainability.
- Access to government incentives is facilitated through the utilization of wind, solar, and hydrogen technologies.
- Air-cooled data centers benefit from economies of scale, optimizing operational efficiency.
- Ergonomically designed CRAC units eliminate the need for server reconfiguration, streamlining maintenance processes.

Costs

- The substantial land requirements, amounting to 1.5 times the total capacity, pose a notable challenge.
- An additional capacity is imperative to support dispatchable power sources, introducing an extra operational burden.
- The implementation of large-scale wind, solar, and hydrogen technologies proves to be financially demanding.
- High latency connections and restricted access to fiber connection lines contribute to limitations in connectivity.



Package 2: Solar and Pumped Hydro Storage





Concept Package 2: Solar + Hydro Storage



Location: Northern Alamosa Country Cooling Method: Traditional Air Cooling (CRAC/CRAH)

Photovoltaic Solar:

- Energy Density of 0.15 MW / acre
- 1.6x the peak demand will be supplied through solar
- Requires ~60 acres of 8 W 2-axis solar arrays

Pumped Hydro Storage:

- Excess generation will be used to pump water from a lower reservoir to a higher reservoir, storing electricity in the form of potential energy
- A standstill to full capacity ramp rate of less than 5 minutes



Concept Package 2: Solar + Pumped Hydro Storage

Benefits

- Integration of a storable renewable energy increases redundancy and fault tolerance.
- Water can be used use in a multitude of uses and cycles.
- Access to government incentives is facilitated through the utilization of solar technologies.
- Using the water responsibly can positively influence the environment.
- Air-cooled data centers benefit from economies of scale, optimizing operational efficiency.
- Ergonomically designed CRAC units eliminate the need for server reconfiguration, streamlining maintenance processes.

Costs

- The substantial land requirements, ~50 acres for the solar and ~20 for the pumped storage.
 - Requires 100m height change for pumped storage
- Large financial obligations for this demand of land.
- Lengthy timeframe in permitting for large solar arrays and pumped storage.
- The location poses a potential latency issue with the lack of fiber interconnections near our location.
- Load diminishes significantly in the winter and at night.
- Pumped storage does not work in sub-freezing temperatures.

Design Decision

Package 3: Geothermal, Hydrogen, and Solar





Concept Package 3: Geothermal + Hydrogen and Solar



Location: El Paso Country, 4230.44 Acres

Cooling Method: 25% Direct-to-Chip Cooling & 75% CRAC/CRAH with aid of Ground-Source heat pump

Deep Enhanced Geothermal Systems:

- Energy Density of 7 MWe/acre
- 1.5x the capacity of the total load
- Requires 3.4 acres of land to achieve this load

Hydrogen Utilization:

- Excess capacity for Hydrogen production with onsite electrolyzer
- 0.5x of total capacity can be supplied by hydrogen fuel cell



Concept Package 3: Geothermal + Hydrogen and Solar

Benefits

- Geothermal provides a non-variable source of energy generation for most of our electric load
- Very high energy density for our renewable energy generation possibilities
- We intend to also have a geothermal heat pump (for cooling) at this site, so the water can be recycled into that
- With all the water we are using at this site, we intend to have direct-to-chip cooling using either water or some other refrigerant
- Geothermal wells require little maintenance to ensure they are running properly

Costs

- Substantial up-front costs for well drilling and boring for geothermal heat pumps
 - Geothermal Energy wells must be drilled anywhere from 1 to 6 miles deep
- Lengthy timeframe in permitting for large-scale geothermal energy generation sites
- We will have large water usage requirements for this site due to the nature of the energy generation and cooling

Site Plan



Floor Plan





SCALE: 1" = 10'

= 2.5'

84 SERVERS PER ROOM

336 TOTAL SERVERS

High-Level Electrical One Line





MINES.EDU

Cooling Calculations

Cooling & Load

	Total Load	Single Server Rack						
Number of Racks	334	1						
Electrical Load	5 MW	15 kW						
Sensible Heat Load (Btu/hr)	1706000 Btu/hr	5108 Btu/hr						
Sensible Heat Load (Ton)	142.16 ton	4.2 ton						
Air Cooling (CFM)	96910 CFM	290 CFM						
Direct-to-Chip (GPM)	170.6 GPM	0.51 GPM						



Schedule & Next Updates

Project Planner

ACTIVITY	PLAN START	PLAN DURATION	PERCENT COMPLETE	9-Nov	10-Nov	11-Nov	12-Nov	13-Nov	14-Nov	15-Nov	16-Nov	17-Nov	18-Nov	19-Nov	20-Nov	21-Nov	22-Nov	23-Nov	24-Nov	25-Nov	26-Nov	27-Nov	28-Nov	29-Nov	30-Nov	1-Dec	2-Dec
Convint A	26.04	52	100%																								
Sprint 4 Complete site plan with building shell	26-Oct	1	100%	******	400000000000000000000000000000000000000	******	911111111111111111111111111111111111111				///////////////////////////////////////		911111111111111111111111111111111111111		900000000000000000000000000000000000000	******	******	*****		******			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	400000000000000000000000000000000000000	900000000000000000000000000000000000000	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	400000000000000000000000000000000000000
Create preliminary mechanical one- lines for viability analysis purposes.	31-Oct	33	100%																								
Create preliminary electrical one- lines for viability analysis purposes	31-Oct	33	100%																								
sources/generation	31-Oct	26	100%																								
Risk analysis	7-Nov	27	75%																								
analysis	7-Nov	27	75%																								
Create PDR Presentation	31-Oct	7	75%																								
PDR Dry run	2-Nov	1	100%																								
Preliminary Design review	7-Nov	1	100%		100000000000000000000000000000000000000	1111111111111111111111111	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	5/////////////////////////////////////							500000000000000000000000000000000000000		100000000000000000000000000000000000000			,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,		*****		,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	500000000000000000000000000000000000000	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	
Next Steps Letter	8-Dec	27	0%																								
Prepare Sprint 5 backlog	5-Dec	1	0%																								
Sprint 4 Reivew	5-Dec	1	0%																								
Plan client action items from PDR	8-Dec	28	0%																								
scheduling/planning	9-Dec	13	0%																								
Sprint 5	5-Dec	4	0%																								
Preliminary redundancy analysis	6-Dec	1	0%																								
Tiering discussion	7-Dec	1	0%																								
PDR Updated Submission	8-Dec	11	0%																								
Project Goal Attainment	8-Dec	4	0%																								
Prepare Sprint 6 Backlog	10-Dec	1	0%																								





Next Steps

- Plan for the spring semester
- Begin redundancy design
 - Cooling
 - Electrical
 - Backup power
- Begin planning for a multi-tenant facility
 - Number of rooms
 - Type of servers
 - Flexibility
- Develop more polished plans
 - Site
 - Utility sources
 - Power generation pathways







Thank you for your time and attention! Questions?

-